

Delhi Transport Corporation
Office of the Dy. CGM(C)-II
Nand Nagri Depot: Delhi

No. Dy. CGM(C)-II/NND/2020/07

Dated: 19-1-2021

Notice Inviting Quotation

Percentage rate quotation are invited for the following work on behalf of the MD, DTC from the registered contractor of CPWD, MES, Railways, DDA, PWD Delhi, NDMC, I&FC, MCD and having work experience certificate with Govt. dept.

Name of work	Estimated Cost	Earnest Money	Time allowed
Renovation of ET plant underground tank at BBM Depot.	Rs.1,78,768.00/-	Rs.3575.00/-	30days

Date and time of receipt of application from the office of Mgr. (C)/PMC, HQ.

...27/1/21

up to 4.00 PM

Date and time of issue of quotation from the office of Mgr. (C) /PMC HQ.

...29/1/21

up to 4.00 PM

Date and time of receipt of quotation in the tender cell room No.-207 at DTC, HQ.

...2/2/21

up to 12.00 PM

Date and time of opening of quotation

...2/2/21

at 3.00 PM

Definition of similar work: Repair and renovation of building works.

Note:

1. The work experience certificate of similar work of any Govt. dept. in the last 7 years shall be submitted along with the application for getting the quotation. The one work of value not less than 80% of the estimated cost or two works each of value not less than 60% of the estimated cost or 3 works of 40% of the estimated cost.
2. The EMD should be deposited in the shape of Cash (in the DTC HQ Cash section), Banker Cheque, Pay Order, Demand Draft and FDR of Schedule Bank in favour of MD, DTC and receipt shall be submitted with bid/quotation.
3. The rates will be quoted/written in words also as well as in number otherwise the quotation will be cancelled.
4. The under signed reserves the right to cancel any /all quotations without assigning any reason thereof.
5. The copy of valid registration as on date with the above departments is to be submitted along with the application for NIQ.
6. The rate should be inclusive of all taxes etc.


Manager(C)H.Q.

Encl: Terms and conditions.

Copy to: 1. Dy.CGM (Civil)-II for information pl.


2. Manager (IT) BBM Complex requested to upload the NIQ on DTC website.
3. Manager, (Tender Cell), DTC, HQ. I.P. Estate for information and to make the arrangement for receipt of quotation and opening as per above schedule.
4. Manager(C) to issue NIQ.
5. Notice Board
6. Master file.

SCHEDULE OF QUANTITY

Name of Work:- Renovation of ET Plant underground tank at BBM Depot.

S.No	DSR-2016	Description of Item	Qty.	Unit	Rate	Amount
1	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	4.00	cum	1454.55	5818.20
2	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	70.00	sqm	22.40	1568.00
3	M/R	Steel cap straightening and welding	5.00	no	600.00	3000.00
4	R/A	Cleaning of ETP Tank mechanically/manually by using suction machine etc. including loading and unloading garbage/malba up to dumping ground.	55.00	cum	284.50	15647.50
5	25	Hire and running charges of light crane for lifting boxes from the top of Tank	2.00	day	2500.00	5000.00
6	6.4.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : a) Cement mortar 1:6 (1 cement : 6 coarse sand)	1.00	cum	5582.85	5582.85
7	13.8.2	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : a) 1:4 (1 cement: 4 fine sand)	70.00	sqm	241.50	16905.00
8	13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade : a) New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	55.00	sqm	96.05	5282.75
9	5.1.3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : a) 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	4.00	cum	5772.65	23090.60
10	5.22A.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. a) Thermo- Mechanically Treated bars of grade Fe-500D or more	500.00	kg	56.60	28300.00
11	5.9.3	Centering and shuttering including strutting, propping etc. and removal of form for all heights : a) Suspended floors, roofs, landings, balconies and access platform	22.00	sqm	422.30	9290.60


12	22.5	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : (a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. This layer will be allowed to air cure for 4 hours. (b) Second layer of slurry of cement @ 0.242 kg/sqm mixed with water proofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry."	150.00	sqm	298.30	44745.00
13	14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) One or more coats on old work	6.00	sqm	51.30	307.80
14	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	10.00	cum	120.55	1205.50
15	M/R	Fixing the existing pipe, fitting ET Plant complete in all respect as per site required.	One job		5000.00	5000.00
		Total				170743.80
		Cost index @ 15.69%			(+)	26789.70
		Total				197533.50
		Less @ 9.5% on DSR 2016			(-)	18765.68
		Total				178767.82
Say						1,78,768/-


Mgr(C)HQ


S.O (C) North

Terms & Conditions: -

1. The work shall be executed as per latest CPWD specifications with correction slip issued up to the date and as per direction of Engineer-in-charge.
2. The contractor shall take all safety measures for satisfactory completion of the work at his own cost and he shall be completely responsible for any mishap occur during execution of the work.
3. No T & P will be provided by the DTC.
4. All valid/mandatory taxes will be deducted as per Govt. rules from contractor bill.
5. Any damage to any part of the building during execution of the work shall be made good by the contractor at his own cost.
6. The contractor shall make his own arrangement for filtered & unfiltered water and electricity for use in construction and for his labour.
7. Contractor shall ensure the payment of workers in minimum wages and other social security scheme like PF, ESI contribution and bonus etc.
8. Contractor shall ensure the payment of revision of minimum wages notified by labour department every year in the month of April & October. This clause shall not only be a statutory obligation on the part of contractors but also shall ensure the legal entitlement to minimum rate of wages to workers.
9. The Officer-in-charge of the work will accept or reject the work executed, according to his judgement.
10. This order can be cancelled /stopped at any time by the officer-in-charge of the work or by any officer superior to him in authority similarly, the contractor is liable to cease work at any time.
11. The rates quoted by the agency shall include all the applicable taxes like GST etc. & nothing extra on account of taxes shall be payable.
12. The 5% security shall be deducted from the running/final payments & same shall be released after a period of 6 months after date of satisfactory completion of the work.
13. The time allowed for carrying out the work in 30 days from the date of issue of work order or handing over of site whichever is later.


Manager(C)H.Q.